



**WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LIMITED**

(A Government of West Bengal Enterprise)

CIN : U40109WB2007SGC113473

VIDYUT BHAVAN : BIDHANNAGAR : KOLKATA - 91

**WBSEDCL**

Office Order No: CED/ 13

Dt: 15.05.2018

**Sub: - Revised rates for new construction works**

Rates, Terms & conditions of the Rate Contract Order for new Construction work are hereby, revised with effect from **1<sup>st</sup> April, 2018 for a period of two years or until further order**. Necessary rates, terms & conditions are mentioned below:

1. This revised schedule of rates for new Construction work shall **not be applicable** for the works for which LOI / orders have been placed before **01-04-2018** and also for cases where the work has already been executed on or before **01-04-2018** and Orders placed as a post facto regularization cases.
2. Rates include cost of transportation of Company's material from Company's Store to the site of work up to a distance of 5 Km. In case, the distance exceeds 5 Km, the Contractor will get transportation charges for excess distances beyond 5 km as per approved slab rate published from time to time by the P&C Department, WBSEDCL.
3. Rates include fabrication cost of all M.S. Sections which will be supplied by the Company for making clamps and other fittings except fabrication of V-Bracket, Top adopter and D-iron clamps. These items will be supplied to the Contractor.
4. (a) If the Company has to supply M. S. Clamps (other than D-Iron Clamps), cost of fabrication is to be realized at the rate of Rs. **2620.00** (Rupees two thousand six hundred and twenty) only per M. Ton of M.S. item.  
( b ) If the Company fails to supply M.S. V-bracket, top adopter & D-Iron Clamp and instead supplies requisite M.S. Section for fabrication of the above 3 ( three) items to the Contractor, fabrication cost at the rate of Rs. **2620.00** (Rupees two thousand six hundred and twenty) only per Metric ton will be allowed.
5. No Controlling Officer / Executive Officer shall engage any Contractor for any new construction job until a LOI or a written permission is given to the Concerned Contractor by mentioning the tentative job to be carried out and place / area of work.
6. Rates includes cost of cement, sand, brick bats, brick ballast, all sorts of M.S. and G.I. Nuts, Bolts, Studs and Washers of approved brand and quality, Cable socketing of Cables, Eye Bolts, G.I. nuts--bolts for fixing shackle insulator with D-Iron Clamps etc. These materials are to be supplied by the contractor.

Payment of bills will be processed after necessary deduction towards Security Deposit, Income tax, adjustment of advance, if any, whenever applicable, along with the consumption of material.

7. Rates with painting of M.S. Section include application of one coat of Red Oxide as primer followed by two coats of aluminum finishing paint of approved brand and quality, and the paints and primer are to be supplied by the Contractor.
  8. Contractors while submitting claims of bills will have to furnish a certificate on demand from the Electrical Supervisor stating that works have been carried out as per Company's specification under his jurisdiction/supervision.
  9. Contractors enlisted under RE wing & Dist. HQ of WBSEDCL having Provident Fund, ESI Registration (in ESI notified area) & **GST Registration** Certificate (valid GSTIN) will only be deployed for this work / contract. However, in case of any ESI non applicability areas, ESI registration is not mandatory, where equivalent mediclaim policy & W.C insurance against the labours needs to be obtained by the agency/contractor. The deployment shall be made considering past satisfactory performance records of the enlisted Contractors. An endeavor shall, however, be made to deploy all the enlisted Contractors within the respective Division in turn or in rotations subject to satisfactory performance.
  10. No Sub-contracting will be allowed for a particular job by the Contractor for execution.
  11. The engaged skilled labors shall posses Workmen's permit for relevant voltage class and shall have the adequate expertise and experience while doing the Construction jobs.
  12. All required matching materials shall be issued by the authorized Officer of WBSEDCL on requisition (SIRN) from the concerned Store. Unnecessary blockage of materials from the Contractor's end shall be treated as disqualification to the contract performance.  
Contractors have to submit a reconciliation statement which should be attached with the claim for verification by the Drawing & Disbursing Officer of the Work.
  13. Additional 30% on rates for new construction works shall be applicable at all the jurisdiction areas under Darjeeling, Kurseong and Kalimpong Divisions and also in the jurisdictional area under Jhalong Paren Customer Care Centre under Mal Division.
- 14. Compliance of Statutory Obligation :**
- 14.1** For the purpose of better and effective compliances of statutory obligation, WBSEDCL has made provisions in rates for reimbursement of **Provident Fund 13.15%, Bonus @ 8.33% & ESI @ 4.75%**. In case of non ESI applicability areas, the same amount i.e. 4.75% of wages should be utilized for purchases of Mediclaim Policy from the govt. Undertaking Insurance Companies in the name of each labour separately. **No Group Mediclaim Insurance will be allowed.**
  - 14.2** Contractors shall ensure that their employees should get wages as fixed at per with the minimum wages as published by the govt. of West Bengal from time to time and Comply with statutory provisions of EPF and miscellaneous provisions Act, 1952, ESI act 1948, Contract Labour (Regulation & Abolitions) Act 1970 and other relevant Labour Laws as well as Circulars / Orders of the Company issued from time to time.
  - 14.3** The Contractor while submitting the bill must enclose Form No. 12A as per EPF scheme, 1952 positively in token of proof towards payment of Provident Fund Contribution to the Provident Fund authority (**Copy of ECR, Temporary Return Reference Number, Remittance Confirmation slip under online method/mode**). The contractor must also submit a statement indicating name of Contractor Labors along with their wages etc. towards deposit of EPF and Pension Fund as per

Circular dated 26-03-2008 of the Director (HR), WBSEDCL, revised time to time and also the confirmation slip of ESI deposition.

**14.4** All controlling officers shall implement the Circular dated 01-12-2005 and subsequent instructions of the Director ( HR) regarding witnessing and authenticating payment of wages including other statutory benefits as well as submission of compliance certificate on monthly basis by an authorized representative of the concerned establishment.

**14.5** The concerned (HR & A) personnel as well as (F & A) personnel of the Establishment must ensure that the Contractor employees as engaged by the contractor are registered as per ESI Act where ESI is applicable. The Contractor is liable to enclose necessary challan towards payment of ESI contribution to the respective ESI Authority where ESI scheme is applicable. Immediately after registration, the concerned (HR & A) personnel must collect photo copy of ESI Identity Card as issued by the ESI Authority in favour of the individual labours.

**14.6** The concerned (HR & A) personnel and concerned (F&A) personnel of the establishment must ensure that the concerned contractor has procured Mediclaim insurance Policy from a Nationalized Insurance Company in respect of each of the Contractor Labour where ESI scheme is not applicable. The quantum of premium of Mediclaim Insurance Policy should be equal to 4.75% of wages of the respective Contract labour.

**14.7** It shall be the personal responsibility of the Officer who awarded the order that adequate personal protective equipments are available with the Contractor and no labour is allowed to undertake any job without informing the concerned officer and without observing the safety standards of the Company. In case of accident while working on the system of WBSEDCL, if it is observed that the Contract Labours had no personal protective equipments and other safety standards were not observed and due to which accident occurred, the order on the concerned Contractor shall be cancelled immediately, in addition to other actions as per Office Order No. 323 dated 12-07-2010 of the Director ( HR), the Circular 1/2012 dated 31-01-2012 of the Director(HR) & the letter to all Zonal managers by the Director(HR) vide Memo No. Safety / 40 / 255 dated 22-01-2013 and **subsequent circulars of Director (HR) issued in 2017 regarding the issue** shall be followed logically in this regard on the merit of the case.

**14.8** If any Contract labour meets with an accident while working in the system of the Company resulting in death or loss of earning capacity of the Labour, his legal heir ( S) / concerned labour ( in case of loss of earning capacity) if entitled for compensation as per Workmen's Compensation Act, 1923 and such compensation shall be paid by the concerned agency/contractor through the Commissioner , Workmen's Compensation, and in case the agency failed to do so the WBSEDCL shall arrange to comply following the guidelines as per Circular No. 2/2011 dated 18-01-2011 of the Director ( HR), WBSEDCL, with a provision to recovery the amount from the contractor/agency as per relevant provision of the Workmen's Compensation Act 1923 (Now Employee's Compensation Act'1923) . Existing Delegation of Power for Distribution Wing shall apply to ascertain the Sanctioning Authority.

## **15. Applicability of taxes & Duties**

**15.1 GST** - The GST as per prevailing rates shall be paid extra to the Contractor having valid GSTIN. The GST, therefore, is paid only to the Registered Contractor under appropriate authority.


**15.2 Income Tax** - As per relevant provisions of Indian Income Tax Act, necessary deduction from the respective bill (s) of the agency on account of Income Tax shall be made. The Drawing & Disbursing Officer will issued necessary TDS certificate accordingly.

15.3 Building & other construction workers welfare cess will be deducted as per provision of the Act.

16. The Concerned (HR & A) personnel of the Establishment shall act as Nodal Officer towards supervision of compliances of all statutory obligations by the contractor.

This has got approval of the Chairman & Managing Director, WBSEDCL

Enclo:- Revised rate for new construction work.

  
10.05.2018.  
(Sujay Sarkar)  
Director (HR)

Memo. No. **CED/452(1-133)**

Dated- **15.05.18**

Distribution

01. The Director : (Distribution)/ (Finance) : WBSEDCL : Vidyut Bhavan : Kolkata- 91.
02. The Director (Project) : WBSEDCL : Vidyut Bhavan : Kolkata- 91.
03. The Chief Engineer : Distribution/ RE/IT&C/ CRM/ DTD/ PTR/ Planning/ Commercial : WBSEDCL.  
----- The CE (IT&C) is requested for uploading the Circular in WBSEDCL's Website
04. The General Manager (HR&A) / (F&A) : Corporate : WBSEDCL : Vidyut Bhavan : Kolkata- 91.
05. The Addl. General Manager (HR&A) / (F&A) : Distribution : WBSEDCL : Vidyut Bhavan: Kolkata- 91.
06. Addl. Chief Engineer (Safety) : WBSEDCL : Vidyut Bhavan: Kolkata- 91.
07. The Zonal Manager : Kolkata/ Burdwan/ Midnapore/ Berhampore/ Siliguri Zone : WBSEDCL
08. The Regional Manager :  
Bidhannagar/ 24-Prgs.(North)/ 24-Prgs.(South)/ Howrah/ Hooghly/ Burdwan/ Birbhum/ Purba Midnapore/ Paschim Midnapore/ Bankura/ Purulia/ Malda/ Murshidabad/ Nadia/ Darjeeling/ Jalpaiguri/ Raiganj/ Coochbehar/ Alipurduar/Dakhin-Dinajpur Regional Office, WBSEDCL.
09. The Project Manager :  
Barasat / Baruipur / Diamond Harbour / Howrah / Hooghly / Burdwan / Purba Midnapore / Paschim Midnapore / Purulia / Suri / Nadia / Malda / Murshidabad / Bankura / Raiganj / Siliguri / Jalpaiguri / Dakshin Dinajpur / Coochbehar / Coochbehar Spl. Project.
10. The Divisional Manager :  
Bidhannagar- I/ Bidhannagar- II/ Barrackpore/ Naihati/ Barasat/ Basirhat/ Bongaon/ Habra/ Uluberia/ Howrah-I/ Howrah- II/ Behala/ Garia/ Baruipore/ Canning/ Diamond Harbour/ Kakdwip/ Serampore/ Chandannagar/ Tarakeswar/ Arambag/ Singur-Haripal/ Mogra/ Memari/ Burdwan Urban/ Burdwan Rural/ Katwa/ Kalna/ Durgapur/ Asansol/ Rampurhat/ Suri/ Bolpur/ Kharagpur/ Belda/ Jhargram/ Midnapur/ Ghatal/ Contai/ Egra/ Haldia/ Tamluk/ Bankura/ Bishnupur/ Khatra/ Purulia/ Raghunathpur/ Kalyani/ Krishnanagar/ Tehatta/ Berhampore/ Raghunathgunj/ Kandi/ Domkal/ Jiaganj/ North Malda/ South Malda/ Raiganj/ Dakshin Dinajpur/ Coochbehar/ Mathabhanga/ Alipurduar/ Jalpaiguri/ Mal/ Siliguri Suburban/ Siliguri Town/ Darjeeling/ Kurseong/ Kalimpong/ Islampur Division : WBSEDCL.
11. The P.S. to Chairman & Managing Director : WBSEDCL : VidyutBhavan : Kolkata- 91.

WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LIMITED

ERCTION RATE FOR NEW CONSTRUCTION WORKS-2018

SL. NO.	DESCRIPTION OF ITEM	UNIT	RATE (In Rs.)		
			WITH PAINTING	WITHOUT PAINTING	
1	SURVEY (PRELIM. & FINAL) FOR HV OH LINE UPTO 33 KV	i)	SURVEY (PRELIM. & FINAL) FOR HV OH LINE UPTO 33 KV	KM	2761.00
2	DO FOR L&MV OH LINE	ii)	DO FOR L&MV OH LINE	KM	1714.00
3	ERECTION OF SINGLE POLE WITH FOUNDATION BUT WITHOUT ANY FITTINGS	i)	RAIL POLE UPTO 12.8 METRE	NO	4351.00
		ii)	SOLID PCC POLE 9 MTR. LONG	NO	2281.00
		iii)	SOLID PCC POLE 8 MTR. LONG	NO	1501.00
		iv)	STEEL TUBULER POLE 9 MTR. LONG	NO	2575.92
		v)	STEEL TUBULER POLE 11 MTR. LONG	NO	3127.30
4	ERECTION OF SINGLE POLE COMPLETE WITH ALL FITTINGS i.e, V-BRACKET, TOP ADAPTOR ETC. AND FOUNDATION BUT WITHOUT ANY INSULATOR FOR HV OH LINE UPTO 33 KV	i)	RAIL POLE UPTO 12.8 MTR. LONG	NO	4141.00
		ii)	SOLID PCC POLE 9 MTR. LONG	NO	2534.00
		iii)	SOLID PPC POLE 8 MTR. LONG	NO	1680.00
		iv)	STEEL TUBULER POLE 9 MTR. LONG	NO	2445.00
		v)	DO BUT 11 MTR. LONG	NO	3221.00
5	ERECTION OF DOUBLE POLE STRUCTURE COMPLETE WITH ALL FITTINGS AND FOUNDATION BUT WITHOUT ANY INSULATOR FOR HV OH LINE UPTO 33 KV	i)	RAIL POLE UPTO 12.81 MTR. LONG	NO	12421.00
		ii)	SOLID PCC POLE 9 MTR. LONG	NO	8922.00
		iii)	SOLID PCC POLE 8 MTR. LONG	NO	5654.00
		iv)	STEEL TUBULAR POLE 9 MTR.	NO	6211.00
		v)	STEEL TUBULAR POLE 11 MTR.	NO	6238.00
6	ERECTION OF TRIPPLE POLE STRUCTURE COMPLETE WITH ALL FITTINGS AND FOUNDATIONS BUT WITHOUT INSULATOR FOR HV OH LINE UPTO 33 KV	i)	RAILPOLE UPTO 12.81 MTR. LONG	NO	20784.00
		ii)	PCC POLE SOLID 9 MTR. LONG	NO	15242.00
		iii)	PCC POLE SOLID 8 MTR. LONG	NO	11012.00
		iv)	STEEL TUBULAR POLE 9 MTR.	NO	17350.00
		v)	STEEL TUBULAR POLE 11 MTR.	NO	17390.00

WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LIMITED

ERCTION RATE FOR NEW CONSTRUCTION WORKS-2018


SL. NO.	DESCRIPTION OF ITEM	UNIT	RATE (In Rs.)	
			WITH PAINTING	WITHOUT PAINTING
7	ERECTION OF FOUR POLE STRUCTURE COMPLETE WITH ALL FITTINGS AND FOUNDATIONS BUT WITHOUT INSULATOR FOR HV OH LINE UPTO 33 KV	i)	RAILPOLE UPTO 12.81 MTR. LONG	NO 35717.00 31675.00
		ii)	PCC POLE SOLID 9 MTR. LONG	NO 27829.68 24572.00
		iii)	PCC POLE SOLID 8 MTR. LONG	NO 15312.00 13334.00
		iv)	STEEL TUBULAR POLE 9 TO 11 MTR.	NO 30314.00 26960.00
8	EXTENSION OF SINGLE POLE COMPLETE WITH ALL FITTINGS UPTO 3 MTR. LENGTH BUT WITH OUT INSULATOR FOR HV OH LINE UPTO 33 KV	i)	RAIL POLE	NO 1862.95 1663.00
		ii)	SOLID PCC POLE 8 MTR. LONG	NO 1706.38 1506.00
9	ERECTION OF SUB-STATION STRUCTURE COMPLETE WITH ALL FITTINGS ie. FITTINGS FOR ISOLATOR , FUSE UNIT , TRANSFORMER ,KIOSK,MS HOOD ,TOP CHANNEL ETC. AND FOUNDATION BUT WITHOUT INSULATOR	i)	RAIL POLE SUPPORT (D.P.)	NO 16112.00 15252.00
		ii)	PCC POLE SOLID 9 MTR. LONG (D.P.)	NO 13169.00 12309.00
		iii)	PCC POLE SOLID 8 MTR. LONG (D.P.)	NO 10735.00 9875.00
		iv)	4 POLE STRUCTURE OF 8 MTR. LONG PCC POLE	NO 19872.00 19012.00
		i)	a) 150 Sq. mm. ACSR 'WOLF' OR EQU. SIZE OF AAAC	3 WIRE KM 19208.00
		ii)		2 WIRE KM 14154.00
		iii)		1 WIRE KM 9246.00
		i)	a) 100 Sq. mm. ACSR 'DOG' OR EQU. SIZE OF AAAC	3 WIRE KM 16544.00
		ii)		2 WIRE KM 12330.00
		iii)		1 WIRE KM 8169.00
		i)	b) 50 Sq. mm. ACSR RABIT OR EQU. SIZE OF AAAC	4 WIRE KM 9715.00
		ii)		3 WIRE KM 8289.00
		iii)		2 WIRE KM 6184.00



## WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LIMITED

## ERCTION RATE FOR NEW CONSTRUCTION WORKS-2018

SL. NO.	DESCRIPTION OF ITEM	UNIT	RATE (In Rs.)			
			WITH PAINTING	WITHOUT PAINTING		
10	ERECTION OF CONDUCTOR INCLUDING LAYING, HOISTING, STRINGING, JOINTING, SAGGING, TENSIONING & ROUTE CLEARANCE	iv)	1 WIRE 4 WIRE 3 WIRE 2 WIRE 1 WIRE	KM KM KM KM KM	2978.00 8821.00 7899.00 5322.00 2845.00	
		i)	c) 30 Sq. mm. ACSR WEASEL OR EQU. SIZE OF AAAC	4 WIRE 3 WIRE 2 WIRE 1 WIRE	KM KM KM KM	8432.00 7043.00 4873.00 2894.00
		ii)		4 WIRE 3 WIRE 2 WIRE 1 WIRE	KM KM KM KM	8432.00 7043.00 4873.00 2894.00
		iii)		4 WIRE 3 WIRE 2 WIRE 1 WIRE	KM KM KM KM	8432.00 7043.00 4873.00 2894.00
		iv)		4 WIRE 3 WIRE 2 WIRE 1 WIRE	KM KM KM KM	8432.00 7043.00 4873.00 2894.00
		i)	d) 20 Sq. mm. ACSR SQUIRREL OR EQU. SIZE OF AAAC	4 WIRE 3 WIRE 2 WIRE 1 WIRE	KM KM KM KM	7972.00 6882.00 4864.00 2815.00
		ii)		4 WIRE 3 WIRE 2 WIRE 1 WIRE	KM KM KM KM	7136.00 6301.00 4412.00 2435.00
		iii)		4 WIRE 3 WIRE 2 WIRE 1 WIRE	KM KM KM KM	7136.00 6301.00 4412.00 2435.00
		iv)		4 WIRE 3 WIRE 2 WIRE 1 WIRE	KM KM KM KM	7136.00 6301.00 4412.00 2435.00
10	ERECTION OF CONDUCTOR INCLUDING LAYING, HOISTING, STRINGING, JOINTING, SAGGING, TENSIONING & ROUTE CLEARANCE	i)	e) 50 Sq. mm. AAC ANT	4 WIRE 3 WIRE 2 WIRE 1 WIRE	KM KM KM KM	7972.00 6882.00 4864.00 2815.00
		ii)		4 WIRE 3 WIRE 2 WIRE 1 WIRE	KM KM KM KM	7136.00 6301.00 4412.00 2435.00
		iii)		4 WIRE 3 WIRE 2 WIRE 1 WIRE	KM KM KM KM	7136.00 6301.00 4412.00 2435.00
		iv)		4 WIRE 3 WIRE 2 WIRE 1 WIRE	KM KM KM KM	7136.00 6301.00 4412.00 2435.00
		i)	f) 25 Sq. mm. AAC GNAT	4 WIRE 3 WIRE	KM KM	7136.00 6301.00
		ii)		2 WIRE 1 WIRE	KM KM	4412.00 2435.00
		iii)		4 WIRE 3 WIRE 2 WIRE 1 WIRE	KM KM KM KM	7136.00 6301.00 4412.00 2435.00
		iv)		4 WIRE 3 WIRE 2 WIRE 1 WIRE	KM KM KM KM	7136.00 6301.00 4412.00 2435.00
		g)	g) 4-5 mm G.I Wire	1 WIRE	KM	1592.00



## WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LIMITED

## ERCTION RATE FOR NEW CONSTRUCTION WORKS-2018

SL. NO.	DESCRIPTION OF ITEM	UNIT	RATE (In Rs.)	
			WITH PAINTING	WITHOUT PAINTING
11	ERECTION OF DISTRIBUTION TRANSFORMER COMPLETE WITH ALL FITTINGS (O/D Type)	i)	10 / 16 KVA 11/0.43KV	NO 1885.00
		ii)	25 KVA 11/0.43KV	NO 1925.00
		iii )	63 KVA 11/0.43KV	NO 2711.00
		iv)	100 KVA 11/0.43KV	NO 3214.00
		v )	315 KVA 11/0.43KV	NO 7248.00
12	A) FABRICATION & FIXING OF CRADLE GUARD BRACKET	i)	SINGLE POLE	NO 237.00
		ii)	DOUBLE POLE	NO 369.00
	B) LEAD WIRE ( a) UPTO 30mtrs.	i)	2 WIRE	NO 256.00
		ii)	4 WIRE	NO 357.00
	DO ( b) ABOVE 30 mtrs. BUT UPTO 60 mtrs.	i)	2 WIRE	NO 312.00
		ii)	4 WIRE	NO 469.00
	DO ( c) ABOVE 60 mtrs. BUT UPTO 100 mtrs.	i)	2 WIRE	NO 506.00
		ii)	4 WIRE	NO 746.00
	C) MAKING & FIXING OF CROSS LESSING WIRE	i)		NO 15.00
13	FIXING OF INSULATOR	I)	11 KV PIN INSULATOR WITH PIN	NO 63.00
		II)	33 KV PIN INSULATOR WITH PIN	NO 72.00
		iii)	11 KV DISC INSULATOR WITH STRAIN HARDWARE	NO 65.00
		iv)	33 KV DISC (i.e. 3 NOS. 11 KV DISC ) INSULATOR WITH STRAIN HARDWARE	NO 107.00
		v)	LT SHACKLE INSULATOR WITH 1 NO. G.I. NUTS & BOLTS	NO 52.00
		vi)	LT SHACKLE INSULATOR (NUTS & BOLTS TO BE SUPPLIED BY BOARDS )	NO 37.00
		vii)	LT PIN WITH INSULATOR	NO 37.00

## WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LIMITED



## ERCTION RATE FOR NEW CONSTRUCTION WORKS-2018

SL. NO.	DESCRIPTION OF ITEM	UNIT	RATE (In Rs.)	
			WITH PAINTING	WITHOUT PAINTING
14	FIXING OF C.I. REEL WITH MS NUTS & BOLTS	i)		46.00
15	STAY SET COMPLETE WITH ALL FITTINGS , GUY - INSULATOR BINDING ETC.	i)	HT STAY SET (1830X20 mm)	NO 641.00
		ii)	LT STAY SET (1630 X 10 mm)	NO 555.00
16	EARTHING COMPLETE WITH DRIVING OF EARTH SPIKE & CONNECTION OF EARTH ELECTRODE WITH NON CURRENT CARRYING METALIC PARTS OF SUPPORTS , STAY WIRES , CRADLE GUARDS , L.A. ETC.		NO	313.00
17	ANTI CLIMBING DEVICE WITH BARBED WIRES		NO	150.00
18	FIXING OF CAUTION BOARD		NO	24.00
19	NUMBERING OF POLES		NO	21.00
20	FIXING OF SAFETY DEVICE ON L&MV O.H. LINE		NO	35.00
21	FIXING OF ANGLE IRON BRACKET ON SINGLE PCC POLE FOR L&MV LINE		NO 605.00	596.00
22	FIXING OF 11 KV T.P.G.O. ISOLATOR ON SUB-STATION STRUCTURE WITH PROPER ADJUSTMENT		NO	1193.00
23	FIXING OF 11 KV T.P.G.O. ISOLATOR ONLINE STRUCTURE (D.P. OR ANY COMPOUND STRUCTURE ) INCLUDING FIXING OF SUPPORTS eg. CHANNEL , CLAMP etc. WITH PROPER ADJUSTMENT		NO 3199.00	3165.00

WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LIMITED

ERCTION RATE FOR NEW CONSTRUCTION WORKS-2018

SL. NO.	DESCRIPTION OF ITEM	UNIT	RATE (In Rs.)	
			WITH PAINTING	WITHOUT PAINTING
24	FIXING OF 11 KV ISOLATING LINK UNIT ON STRUCTURE WITH PROPER ADJUSTMENT	NO	0.00	986.00
25	FIXING OF 11 KV LIGHTNING ARRESTER ON STRUCTURE (1 SET OF 3 L.A.s)	NO	0.00	339.00
26	FIXING OF MS BOX BRACKETS ON POLE FOR L & MV LINE	NO	1433.00	1414.00
27	FIXING OF MAIN SWITCH AND MS HOOD AND COMPLETE CONNECTION WITH PVC CABLE	i)	SINGLE SWITCH	NO 1081.00 1057.00
		ii)	DOUBLE SWITCH	NO 1636.00 1606.00
28	FIXING OF KIOSK AND MAIN SWITCH AND COMPLETE CONNECTION WITH PVC CABLE	i)	SINGLE SWITCH	NO 2238.00 2155.00
		ii)	DOUBLE SWITCH	NO 3100.00 3012.00
29	FIXING OF SOLID TEE OFF BRACKET WITHOUT INSULATOR	i)	SINGLE POLE	NO 1510.00 1495.00
		ii)	DOUBLE POLE	NO 1498.00 1483.00
30	RAIL POLE CUTTING	i)	NO	394.00
31	MAKING HOLE ON RAIL POLE	i)	NO	110.00
32	FIXING OF LT SPACER WITH L & MV H.O.	i)	1-PHASE UNIT	NO 37.00
		ii)	3-PHASE UNIT	NO 56.00
33	FIXING OF MS HOOD ONLY	i)	NO	543.00 519.00



**WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LIMITED**

**ERCTION RATE FOR NEW CONSTRUCTION WORKS-2018**

SL. NO.	DESCRIPTION OF ITEM	UNIT	RATE (In Rs.)	
			WITH PAINTING	WITHOUT PAINTING
34	Fitting/fixing of Dead End/Tension Clamp including compression joint with Wolf Conductor/per cond	i)	NO	201.00
	Fittings/Fixing of Suspension clamp for Wolf Conductor/cond	ii)	NO	30.00
	Fitting/fixing of jumper for wolf conductor with compression joint/cond	iii)	NO	148.00
	Jointing of Wolf Conductor by compression Joint per cond.	iv)	NO	244.00
35	Providing Muffing at the base of Steel Tubular Pole with cement concrete (1:3:6) including shuttering, the muffing should be 600 mm above G.L and 150 mm below G.L and Top should be chamfered		NO	774.00
<p>NB - THE SCHEDULE INCLUDES ERECTION OF EACH RAIL POLE WITH 450X100MM THICK CEMENT CONCRETE (1:3:6) BASE BLOCK BELOW POLE AND HARD JHAMA METAL CEMENT CONCRETE (1:2:4) WITH 0.30 MTR. MUFFING ABOVE GROUND LEVEL INCLUDING NEAT CEMENTED FINISH.</p>				

